BRUHATH BANGALORE MAHANAGARA PALIKE,
Dasarahalli Zone

Office of the Executive Engineer Project Division,
Dasarahalli Zone, Bangalore-73

TENDER SCHDULE-B

Providing Saftey Grill work over the Existing Boundry fencing at Abbigere Hospital park, in Ward -12

Sl. No.	Qty	Description of Work	Unit
1	307.20	Providing & fixing M.S.Grill over existing compound wall as per Chief Architect drawing No. 12686.Using 16mmx 16mm M.S. Square rod at 150mm c/c spacing and 6,,x40mm M.S. flats at horizontal and 6mmx 12mm M.S flat for ornamental design and provding shop edge design at the vertex of every vetical rods including welding, grinding wherever necessary. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint)etc complete. The work includes cost of all materials labour charges for all items of work hire charges for welding, cutting and grinding equipment and electricity charges etc,	cum

"DTS Approved"

Signature of the Contractor

Executive Engineer
Project Division, Dasarahalli Zone
B.B.M.P. Bangalore

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.